

SECTION A - A'

WORK AREA

CRANE PAD

CONSTRUCTION SITE LAYOUT TYPE A

CRANE PAD

WIND TURBINE GRAVEL PAD (MATCH EDGE OF TURBINE FOUNDATION)


WORK AREA

CRANE PATH


ACCESS ROAD

WIND TURBINE



















8 CONSTRUCTION SITE LAYOUT TYPE C
C-601 N.T.S.

FOR PERMITTING ONLY NOT FOR CONSTRUCTION

Environmental
Design & Research,
Landscape Architecture, Engineering
& Environmental Services, D.P.C.

217 Montgomery Street, Suite 1000
Syracuse, New York 13202
P. 315.471.0688

everpewer

| DRAWING REVISIONS | DATE | REVISION | BY Landscape Architecture, Engineering, & Environmental Design & Research, | Landscape Architecture, Engineering, & Environmental Services, D.P.C. | The following is paraphrised from the New York Education | Law, Article 145, Section 7209, and Chapter II, Section 1209, and Chapter II, Section 7209, and Chapter II, Section 72

WINDS PROJECT

SHOCTON, DANSVILLE, FREMONT, AND WAYLAND UNTY, NEW YORK

DINGS

PROJECT TITLE: BARON WINDS

TOWNS OF COHOCTON, DANS
PROJECT LOCATION: STEUBEN COUNTY, NEW YORK

CLIENT: EVERPOWER WIND HOLDINGS

DRAWING THE: TYPICAL CIVIL DETAILS

DATE: NOVEMBER 17, 2017

SCALE: AS NOTED


edr Job#: 13039

DRAWN BY: AW, CB, ZR, JC, KZ

FILE NAME:

FILE NAME: 13039-Details.dwg

C-601



75' TYP.

METEOROLOGICAL TOWER


DISTURBANCE LIMIT NOTES:
1. CONTRACTOR SHALL RESTORE ALL DISTURBED AREAS OUTSIDE OF PERMANENT GRADING TO PRE-CONSTRUCTION CONDITION.
2. CLEARING SHALL BE LIMITED TO DISTURBANCE LIMIT.
3. APPROXIMATE DISTANCE FOR LIMITS OF DISTURBANCE IS SHOWN. AREA SPECIFIC LIMIT OF DISTURBANCE WILL BE SHOWN ON FINAL CONSTRUCTION DOCUMENTS.

METEOROLOGICAL TOWER


LIMITS OF DISTURBANC, TYP.

GRAVEL PAD

- ACCESS ROAD



UNDERGROUND OR OVERHEAD COLLECTION LINE



DISTURBANCE LIMITS

FOR PERMITTING ONLY NOT FOR CONSTRUCTION

Environmental
Design & Research,
Landscape Architecture, Engineering
& Environmental Services, D.P.C. 217 Montgomery Street, Suite 1000 Syracuse, New York 13202 P. 315.471.0688 everpewer 2 - 4 6


**BARON WINDS PROJECT** 


DATE: NOVEMBER 17, 2017 SCALE: AS NOTED

DRAWN BY: AW, CB, ZR, JC, KZ

13039-Details.dwg DRAWING NUMBER:

C-602






## **CULVERT NOTES:**


- 1. ALL BACKFILL SHALL BE COMPACTED TO 95% STD. PROCTER.
- 2. CULVERT SIZE: THE CROSS SECTIONAL AREA OF THE CULVERT PIPE SHALL BE THE LARGEST PIPE DIAMETER EQUAL TO THE UNDISTURBED CROSS SECTIONAL AREA OF THE BANK FULL CONDITION OF THE STREAM. IT SHOULD FIT INTO THE EXISTING CHANNEL WITHOUT EXCAVATION OF THE WATERWAY CHANNEL OR MAJOR APPROACH FILLS. IF A CHANNEL WIDTH EXCEEDS 3 FEET, ADDITIONAL PIPES MAY BE USED UNTIL THE CROSS SECTIONAL AREA OF THE PIPES APPROACHES THE EXISTING CHANNEL. THE MINIMUM CULVERT SIZE SHALL BE AN 18" DIAMETER PIPE.
- 3. TEMPORARY INLET AND OUTLET PROTECTION SHALL BE INSTALLED AS DETAILED


### 4. MULTIPLE PIPE INLETS:

- 4.A. CULVERT LENGTH: THE CULVERTS SHALL EXTEND TO THE UPSTREAM AND DOWNSTREAM TOE OF SLOPE.
- 4.B. MULTIPLE CULVERTS SHALL BE SET SO THEY HAVE A MINIMUM OF 12" SEPARATION FROM OUTSIDE PIPE TO OUTSIDE PIPE.
- 4.C. THE INVERT ELEVATIONS OF THE CULVERT SHALL BE INSTALLED AT OR BELOW THE NATURAL STREAMBED GRADE TO MINIMIZE INTERFERENCE WITH FISH
- 4.D. THE CULVERT SHALL BE COVERED WITH A MINIMUM OF TWO FEET AGGREGATE.










## SECTION B-B'







FOR PERMITTING ONLY NOT FOR CONSTRUCTION



everpewer

>	DRAWING REVISIONS	
	REVISION	©2016 Environmental Design & Research, BY Landscape Architecture, Engineering, 2 Environmental Services D.D.C.
		The following is paraphrased from the New York Education Law, Article 145, Section 7209, and Chapter II, Section
		79-1.4, and applies to this drawing: "It is a violation of this law for any person unless he is acting under the direction of a licensed professional provinces incored bandsons.
1		architect or licensed land surveyor to alter an item in any way. If an item bearing the seal of an engineer, landscape
1		architect or land surveyor is altered, the altering engineer, landscape architect or land surveyor shall affix to the item his cool and the proteins "altered by "followed by his
ı		ins sea and the the incaton attend by londway by instigution and the date of such alteration and a specific description of the alteration.


**WINDS** BARON


PROJECT

DATE: **NOVEMBER 17, 2017** SCALE: **AS NOTED** DRAWN BY: AW, CB, ZR, JC, KZ


13039-Details.dwg

DRAWING NUMBER: C-603







**VEGETATION PROTECTION** 



- 1. AREA CHOSEN FOR STOCKPILING OPERATIONS SHALL BE DRY AND STABLE
- 2. MAXIMUM SLOPE OF STOCKPILE SHALL BE 2H:1V. MAXIMUM HEIGHT SHALL BE 12 FEET
- 3. EACH PILE SHALL BE SURROUNDED WITH SILT FENCING, INSTALLED PER CORRESPONDING DETAIL, THEN STABILIZED WITH ANNUAL GRAIN WITHIN 3 DAYS.
- 4. A PERIMETER DIKE/SWALE SHALL BE LOCATED UP-SLOPE OF THE TOPSOIL STOCKPILE.








NOT TO SCALE


1. STONE SHALL BE PLACED ON A FILTER FABRIC FOUNDATION TO THE LINES, GRADES AND LOCATIONS SHOWN IN THE PLAN.

CONSTRUCTION SPECIFICATIONS

- 2. EXTEND THE STONE A MINIMUM OF 1.5 FEET BEYOND THE DITCH BANKS TO PREVENT CUTTING AROUND THE DAM.
- 3. ENSURE THAT CHANNEL APPURTENANCES SUCH AS CULVERT ENTRANCES BELOW CHECK DAMS ARE NOT SUBJECT TO DAMAGE OR BLOCKAGE FROM DISPLACED STONE. 4. MAXIMUM DRAINAGE AREA 2 ACRES








- 1. PREFABRICATED TEMPORARY CHECK DAMS SHALL BE EITHER URETHANE FOAM (CFC FREE) COVERED WITH GEOTEXITLE FABRIC, TRIANGULAR SILT DIKE BY ACF OR EQUAL.
- 2. ALTERNATELY, HDPE TEMPORARY CHECK DAMS, GEORDIGE BY NILEX OR EQUAL, MAY BE USED. INSTALL PER MANUFACTURER'S INSTRUCTIONS.
- 3. STAPLES SHALL BE PLACED WHERE UNITS OVERLAP AND A DIRECTED BY MANUFACTURERS



PREFABRICATED TEMPORARY CHECK DAM



DATE: NOVEMBER 17, 2017 SCALE: **AS NOTED** DRAWN BY: AW, CB, ZR, JC, KZ 13039-Details.dwg


FOR PERMITTING ONLY NOT FOR CONSTRUCTION

217 Montgomery Street, Suite 1000 Syracuse, New York 13202 P. 315.471.0688 everpewer


Design & Research,

Landscape Architecture, Engineering & Environmental Services, D.P.C.

DRAWING NUMBER: C-604




SLOPE	VEG. FILTER STRIP
	LENGTH
0-8%	50' MIN
8-12%	75' MIN.
12-15%	100' MIN.



2 LEVEL SPREADER TYPICAL SECTION

605 Scale: NTS

605 Scale: NTS



TYPICAL DRY SWALE

Scale: NTS

FOR PERMITTING ONLY NOT FOR CONSTRUCTION

Design & Research,
Landscape Architecture, Engineering
& Environmental Services, D.P.C. 217 Montgomery Street, Suite 1000 Syracuse, New York 13202 P. 315.471.0688 everpewer 2 0 - 0 4

JECT TITLE: BARON WINDS PROJECT
JECT LOCATION: TOWNS OF COHOCTON, DANSVILLE, FREMONT, AND WAYLASTEUBEN COUNTY, NEW YORK
INT: EVERPOWER WIND HOLDINGS

DATE: NOVEMBER 17, 2017

SCALE: AS NOTED


edr Job#: 13039


DRAWN BY: AW, CB, ZR, JC, KZ

FILE NAME:

13039-Details.dwg

C-605







- 1. EXCAVATED TRENCH AND BORE/RECIEVING PIT MATERIAL SHALL BE STOCKPILED ADJACENT TO THE TRENCH, NO CLOSER THAN 10' FROM THE
- TOP OF THE DITCH. 2. SILT FENCE SHALL BE INSTALLED BETWEEN THE STOCKPILED MATERIAL AND BORE/RECIEVING PIT AND THE TOP OF BANK ON BOTH SIDES OF THE STREAM.
- 3. IMMEDIATELY AFTER CONSTRUCTION IS COMPLETE, PERMANENT STABILIZATION MEASURES SHALL BE APPLIED. THERE SHALL BE NO DISTURBANCE TO THE STREAM DURING CONSTRUCTION. 5. REFER TO ELECTRICAL DESIGN FOR CONDUIT DEPTH, TRENCH DETAILS AND
- 6. REFER TO ELECTRICAL ENGINEERING DRAWINGS AND SPECIFICATIONS BY

# COLLECTION LINE

HORIZONTAL DIRECTIONAL DRILLING (HDD) DETAIL FOR STREAM OR WETLAND CROSSINGS





### SECTION VIEW

- NOTES:

  1. TEMPORARY SAND BAGS AND CONDUIT ARE TO BE INSTALLED PRIOR TO ANY CONSTRUCTION WITHIN THE LIMITS OF THE DITCH OR STREAM. IN THE EVENT THAT THE DITCH/STREAM IS DRY DURING CONSTRUCTION AND NO RAIN IN
- FORCAST, SAND BAGS AND CONDUIT ARE NOT NECESSARY. 2. EXCAVATED TRENCH MATERIAL SHALL BE STOCKPILED ADJACENT TO THE TRENCH, NO CLOSER THAN 25' FROM THE TOP OF BANK OF THE
- 3. SILT FENCE SHALL BE INSTALLED BETWEEN THE STOCKPILED MATERIAL AND THE TOP OF BANK OF THE DITCH/STREAM.
- 4. IMMEDIATELY AFTER CONSTRUCTION IS COMPLETE, PERMANENT
- STABILIZATION MEASURES SHALL BE APPLIED. 5. REFER TO ELECTRICAL DESIGN FOR CONDUIT DEPTH AND TRENCH DETAILS.
- 6. REFER TO ELECTRICAL ENGINEERING DRAWINGS AND SPECIFICATIONS BY

COLLECTION LINE CABLE TRENCHING FOR CUT DITCH/TILE OR SELECT STREAM CROSSING
N.T.S.

**BARON WINDS PROJECT** 

Design & Research,

Landscape Architecture, Engineering & Environmental Services, D.P.C.

217 Montgomery Street, Suite 1000 Syracuse, New York 13202 P. 315.471.0688

everpewer

•
DATE: NOVEMBER 17, 2017
SCALE: <b>AS NOTED</b>
edr Job#: 13039
DRAWN BY: AW, CB, ZR, JC, KZ
FILE NAME:

13039-Details.dwg

DRAWING NUMBER:

C-606

FOR PERMITTING ONLY NOT FOR CONSTRUCTION